

ITEM NO	DESCRIPTION	QUANTITY	UNIT
3A/	<p>BILL NO-03 FURNITURE WORKS</p> <p>FURNITURE WORKS</p> <p>General Note : Allow for Table tops, Side Panel and Credenza units use by Melamine or equivalent type plastic Laminated sheet</p> <p>Plastic Laminate sheeting shall be of an approved brand, type, colour etd as directed by the consultant</p> <p>Main Lobby and Reception Area</p> <p>Area D</p>		<p>Note</p> <p>Note</p>
3A/01	<p>Reception Table (D1) Supplying and placing of Reception Table having overall size to 1350x500x1100mm and including 25mm white melamine table top and side panel, front panel and shelf to be 18mm and 10mm thick flat edge clear glass panel fixed on the top of counter. Front and side facia clad with 25mm thick Palette timber plank and make 10mm groove and complete all in accordance to the details drawing Rate inclusive of supplying and fixing of Mobile drawer pedestal</p>	1.00	Nr
3A/02	<p>Company Logo (D4) Supplying and fixing of company logo including 1500x2850mm size Logo including 10mm thick clear acrylic panel and LED back lit system and complete all in accordance to the details drawing</p>	1.00	Nr

3A/03	<p>Area B</p> <p>Manager Table (B1/B2)</p> <p>Supplying and placing of Manager Table and side return having overall size to be 1200x750x750mm, 900x400x750mm and including 20mm thick Grain Melamine table top and side panel, front panel and shelf drawer faces to be 18mm white melamine. all Exposed edges should be finish with PVC edging and complete all in accordance to the detail drawing</p>	2.00	Nr
3A/04	<p>Cupboard unit (B3)</p> <p>Supplying and installing cupboard having overall size to be 1200x400x850mm and including 20mm thick Grain melamine to and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	2.00	Nr

3A/05	<p>Glass Maggi Board (B4) Supplying and fixing of Glass Maggi Board Having Overall size to-1200x750mm including 8mm thick Temper glass with flat edging and white painted and connect to the wall using S/S glass connectors and complete in all accordance to the detail drawing</p>	2.00	Nr
3A/06	<p>Area A Manager Table (A1/A2) Supplying and placing of Manager Table and side return having overall size to be 1200x750x750mm, 900x400x750mm and including 20mm thick Grain Melamine table top and side panel, front panel and shelf drawer faces to be 18mm white melamine. all Exposed edges should be finish with PVC edging and complete all in accordance to the detail drawing</p>	4.00	Nr
3A/07	<p>Cupboard (A4) Supplying and installing cupboard having overall size to be 1650x400x850mm and including 20mm thick Grain melamine top and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	2.00	Nr
Area E			

3A/08	<p>Two In a Cluster Executive Table (E1) Supplying and placing of Two cluster Executive Table and side return having overall size to be 1200x1000x750mm, 400x700x750mmx2 Nr and including 20mm thick Grain Melamine table top and side panel, front panel and shelf drawer faces to be 18mm white melamine. all Exposed edges should be finish with PVC edging and complete all in accordance to the detail drawing. Rate shall inclusive of 1300x300mm size 8mm flat edge finish clear glass separator fixed table as per given detail drawing</p>	2.00	Nr
3A/09	<p>Cupboard (E2) Supplying and installing cupboard having overall size to be 1500x350x850mm and including 20mm thick white melamine top and doors, side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/10	<p>Cupboard (E3) Supplying and installing cupboard having overall size to be 1500x350x1800mm and including 20mm thick white melamine top and doors, side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/11	<p>Glass Maggi Board (E4) Supplying and fixing of Glass Maggi Board</p>		

	<p>Having Overall size to-1200x750mm including 8mm thick Temper glass with flat edging and white painted finish and connect to the wall using S/S glass connectors and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/12	<p>Area G Executive Table (G1/G2) Supplying and placing of Manager Table and side return having overall size to be 1200x600x750mm, 900x400x750mm and including 20mm thick Grain Melamine table top and side panel, front panel and shelf drawer faces to be 18mm white melamine. all Exposed edges should be finish with PVC edging and complete all in accordance to the detail drawing</p>	2.00	Nr
3A/13	<p>Cupboard unit (G3) Supplying and installing cupboard having overall size to be 1200x400x850mm and including 20mm thick Grain melamine to and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/14	<p>Glass Maggi Board (G4) Supplying and fixing of Glass Magi Board Having Overall size to-1200x750mm including 8mm thick Temper glass with flat edging and white painted and connect to the wall using S/S glass connectors and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/15	<p>Area F Six In a cluster with one side return (F1) Supplying and fixing of six in a cluster unit</p>		

	<p>having overall size to be 4500x1300x750, 900x400x750mm and including 20mm thick Grain melamine table top and side panel and shelf to be 18mm white melamine and all exposed edges of table having a PVC Engine. Glass separation unit having overall size to be 4500x50x2250mm and including 10mm thick flat edge Tempered glass panel mounted to floor using steel painted box bar structure with 20mm white melamine lamination board and complete in all accordance to the detail drawing. Rate inclusive of 6 Nos of Mobile drawer pedestal</p>		
3A/16	<p>Wall mounted console grid (F4 & F3) Supplying and fixing of wall mounted console unit including 25x25mm sectional size 1.6mm thick M/S Painted box bar mounted floor, wall and ceiling as shown in gived detail drawing and 18mm thick melamine shelf with pvc edging fixed on box bar frame work and complete in all accordance to the detail drawing Grid width -400mm and Length -10450mm</p>		Item
3A/17	<p>Cupboard unit (F4) Supplying and installing cupboard having overall size to be 1200x400x850mm and including 20mm thick Grain melamine to and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/18	<p>Glass Maggi Board (F5) Supplying and fixing of Glass Maggi Board Having Overall size to-1200x750mm including 8mm thick Temper glass with flat edging and</p>		

	white painted and connect to the wall using S/S glass connectors and complete in all accordance to the detail drawing	1.00	Nr
3A/19	<p>Area C</p> <p>Coffee Table (C1)</p> <p>Supplying and Placing of Coffee table Having Overall size to be 750x750x450mm Including table top to be 8mm clear tempered glass with flat edge finish and glass top fixed on 25x25x3mm 'L' angle bar and 40x3mm flat bar Steel base (black matt eggshells paint finish) and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/20	<p>Console unit (C2)</p> <p>Supplying and Placing of Console unit Having Overall size to be 1800x300x900mm Including table top to be 8mm clear tempered glass with flat edge finish and glass top fixed on 25x25x3mm 'L' angle bar and 40x3mm flat bar Steel base (black matt eggshells paint finish) and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/21	<p>Area L</p> <p>Six In a cluster (L1)</p> <p>Supplying and fixing of six in a cluster unit having overall size to be 4500x1300x750, and including 20mm thick</p>		

	<p>Grain melamine table top and side panel and shelf to be 18mm white melamine and all exposed edges of table having a PVC Engine. Glass separation unit having overall size to be 4500x50x2250mm and including 10mm thick flat edge Tempered glass panel mounted to floor using steel painted box bar structure with 20mm white melamine lamination board and complete in all accordance to the detail drawing. Rate inclusive of 6 Nos of Mobile drawer pedestal</p>		Item
3A/22	<p>Hot Desk (L2) Supplying and fixing of Hot Desk having overall size to 3600x500x1050mm and including 20mm thick Grain Melamine table top and Modesty panel and side panel to be 18mm white melamine and all exposed edges to be PVC edging and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/23	<p>Hot Desk (L2) Option Supplying and fixing of Hot Desk having overall size to 3600x500x1050mm and including 20mm thick Grain Melamine table top and 50x50mm painted M/S box bar base and all exposed edges to be PVC edging and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/24	<p>Filing Unit(L3) Supplying and installing cupboard having overall size to be 2500x300x1050mm and including 20mm thick Grain melamine top and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm</p>		

	<p>white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/25	<p>Wall mounted console grid (L4 & L5) Supplying and fixing of wall mounted console unit including 25x25mm sectional size 1.6mm thick M/S Painted box bar mounted floor, wall and ceiling as shown in give detail drawing and 18mm thick melamine shelf with pvc edging fixed on box bar frame work and complete in all accordance to the detail drawing Grid width -300mm and Length -11500mm</p>		Item
3A/26	<p>Area M Pantry Unit (M1) Supplying and fixing of Pantry cupboard having overall size to be Bottom cupboard -2500x600x850mm Top cupboard - 3000x350x600mm Bottom cupboard including 20mm thick absolute black granite top and sid panels, shelf's, doors and drawer faces to 18mm Eco board with paint finish and Stainless steel hairline finish single bowl single drain sink and swan head tap fixed to the bottom part of pantry. Top cupboard including 18mm white melamine side panels, doors and top, middle, bottom shelf's. All edged to be PVC edging and top and bottom cupboard unit complete in all accordance to the detail drawing with all necessary accessories and fittings Rate inclusive of back flash should be 600x600mm</p>		Item
3A/27	<p>wall tiling finish as per given detail</p> <p>Cupboard (M2) Supplying and installing cupboard having overall size to be 950x450x850mm and including 20mm thick Eco board paint finish top and doors and side panel and shelf to be 18mm</p>		

	<p>Eco board with paint finish and back panel should be 9mm Eco board. complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing</p>	1.00	Nr
3A/28	<p>Dining Table (M3) Supplying and fixing of Dining table having overall size to 500x500x750mm and including 25mm thick Paint finish Eco board top and 75mm diameter Hollow tubular bar fixed to the 350x350mm M/S Painted base plate and complete in all accordance to the detail drawing</p>	2.00	Nr
3A/29	<p>Location K Discussion Table (K1) supplying and fixing of Discussion table having overall size to be 1000mm dia meter and 750mm height and including 25mm thick MDF Painted or Eco board paint finish table top fixed on 50x25mm sectional size M/S painted box bar base and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/30	<p>Pallet Timber Table (K4) Pallet timber table having overall size to be 900x750x750mm and table made out of pallet timber and complete in all accordance to the detail drawing</p>	1.00	Nr
3A/31	<p>Area O Table Supplying and fixing of Table Having overall size to be 1000x600x750mm and including 20mm thick Grain melamine Table top and Side panel and center support to be 18mm white melamine and all edges to be finish with PVC edging</p>		

	and complete in all accordance to the detail drawing	2.00	Nr
3A/32	<p>Area N</p> <p>Filing cupboard (N1)</p> <p>Supplying and fixing of Cupboard unit having overall size to be 2910x400x2100mm and complete in all accordance to the detail drawing with all necessary accessories and fittings</p>	1.00	Nr
3A/33	<p>Filing cupboard N2</p> <p>Supplying and fixing of Cupboard unit having overall size to be 2000x400x2100mm and complete in all accordance to the detail drawing with all necessary accessories and fittings</p>	1.00	Nr
3A/34	<p>Area I</p> <p>Filing cupboard (I2)</p> <p>Supplying and fixing of Cupboard unit having overall size to be 4800x600x3600mm and complete in all accordance to the detail drawing with all necessary accessories and fittings</p>	1.00	Nr
3A/35	<p>Area H</p> <p>Existing Filing cupboard modification work</p> <p>Supplying and fixing of new cupboard doors for existing cupboard including 25mm thick teak timber paint finish Door sash fixing to existing cupboard with approved quality conceal hinges, door lock and complete in all accordance to the detail drawing</p>		Item
3A/36	<p>Wall mounted console grid (H2)</p> <p>Supplying and fixing of wall mounted console unit including 25x25mm sectional size 1.6mm thick M/S Painted box bar mounted floor, wall and ceiling as shown in gived detail drawing and 18mm thick melamine shelf with pvc edging fixed on box bar frame work and complete in all accordance to the detail drawing</p>		

	Grid width -300mm and Length -2400mm	1.00	Nr
	Area J		
	Board Room Table Existing Board room modification work including Removing existing glass top and replace new melamine top as per given detail drawing	1.00	Nr
3A/37	Cupboard unit (J2) Supplying and installing cupboard having overall size to be 1200x400x850mm and including 20mm thick Grain melamine to and 18mm thick grain melamine cupboard doors and side panel and shelf to be 18mm white melamine and back panel should be 9mm white melamine. All exposed edges to be finish with PVC engine and complete with approved quality door hinges, door handles and necessary accessories and fittings and accordance to the detail drawing	1.00	Nr
3A/38	Glass Maggi Board (J3) Supplying and fixing of Glass Magi Board Having Overall size to-1200x750mm including 8mm thick Temper glass with flat edging and white painted and connect to the wall using S/S glass connectors and complete in all accordance to the detail drawing	1.00	Nr
	TOTAL OF FURNITURE WORK CARRIED TO SUMMARY		

4A/	BILL NO-04 CHAIRS CHAIRS IN GROUND FLOOR (IN BUILDING C)		
4A/01	Main Lobby and Reception Area		
4A/01	Supplying of chairs including Mesh Medium back rest with arm, height adjustable		

	with 5 nylon castors (Refer the given detail)	7.00	Nr
4A/02	Supplying of chairs for visitors Including Code No -MXAC-04	6.00	Nr
4A/03	Supplying of Stackable/Foldable chairs	14.00	Nr
4A/04	Supplying of Fancy chairs	4.00	Nr
4A/05	Supplying of Bean Bags	2.00	Nr
4A/06	Supplying timber chairs	1.00	Nr
4A/07	Supplying and fixing of Timber bench	1.00	Nr
4A/06	Supplying dining chairs	4.00	Nr

Supplier Description and Specifications	Price

--	--





















